

BIN BAY SCREEN HOARDING - PRICED BUILD SHEET

Ref TW-BINS-001 Rev P01 4 October 2026

NOT A DESIGN - NOT FOR CONSTRUCTION - NOT A PERMIT TO LOAD

Indicative UK supply rates, 4 Oct 2026, C24 treated softwood from a merchant, delivered. Excludes overheads, profit, prelims, plant hire, waste removal, design fees and the temporary works check.

Description	Qty	Unit	Rate	Amount
A. TIMBER				
Post 75 x 225 C24 treated, 2.40 m long	7	no	27.50	192.50
6 required + 1 waste. 4 to the front run, 2 at the return ends				
Rail 100 x 75 C24 treated, laid flat	27.7	m	8.20	227.14
25.2 m measured (3 levels: 18.0 m front + 7.2 m returns) + 10% waste				
Gate frame 75 x 50 C24 treated	9	m	4.20	37.80
2 stiles 2.10, 2 rails 1.20, 1 diagonal brace 2.40 = 9.0 m				
B. BOARDING				
18 mm OSB/3 sheet 2440 x 1220	9	sheet	29.50	265.50
5 front run + 2 returns + 1 gate leaf + 1 waste				
C. FIXINGS				
Screw 5.0 x 100, rail to post	200	no	0.23	46.00
About 60 to the rails at 4 per connection + 112 boards to rails				
Screw 4.0 x 50, board to rail and gate	100	no	0.10	9.50
Boards to rails and the gate frame				
Tee hinge, galvanised, 300 mm	1	pair	29.00	29.00
Gate leaf, hung on post P2				
Sliding bolt, galvanised, 150 mm	1	no	13.50	13.50
Gate leaf, keep on post P3				
D. GROUNDWORKS				
Break out and excavate 400 mm dia x 900 mm deep, through tarmac	6	hole	48.00	288.00
Hand dig and break out. CAT scan and service check assumed done separately				
Mass concrete C20/25, placed full depth	0.71	m3	148.00	105.08
0.113 m3 per hole x 6 = 0.68 m3 + 5%				
Tarmac reinstatement around each post	6	hole	42.00	252.00
About 0.4 m2 per hole. CONFIRM the surface may be broken - open input				
E. SUNDRIES				
Sealant, washers, cutting, general consumables	1	item	65.00	65.00
Allowance				
F. LABOUR				
Carpenter, erecting	3	day	245.00	735.00
2 carpenters x 1.5 days: set out, posts, rails, facing, gate				
General labourer	1	day	185.00	185.00
Assisting and clearing				

Materials and groundworks	1,531.02
Labour	920.00
TOTAL - excludes overheads, profit and prelims	2,451.02
Rate per metre of hoarding (8.40 m run)	291.79

WHAT THE PRICE DOES NOT INCLUDE

- Overheads, profit and prelims. Plant hire. Waste removal.
- The temporary works design and its independent check - that is the designer's fee.
- A CAT scan and service check before the holes are broken out.
- Any fixing back to the building wall, if the designer calls for one.
- Repainting or making good the wall behind the hoarding.
- Design changes if the ground comes back worse than 'average'. If it is poor, the
- planting depth rises and the price with it.

Rates are indicative. Replace them with the rate book before this is used commercially.